

ADDENDUM TO RFP NO. 212

Amended Scope of Work for RFP No. 212

Please include the additions below to the original scope of work presented in RFP No. 212.

- The majority of the existing ceiling insulation was missing, damaged, and/or out of place. Additionally, the existing insulation is not compliant with the current building code. The existing insulation at the ceiling is R13. Per the current code, the insulation at the ceiling area will be required to have an R38 value.
- The plans show electrical at the far west wall which is a cement masonry unit wall. This will require a framed 2 x 4 wall furred out from the existing cement wall, so as to accommodate the necessary electrical shown in the approved plans.

OFY-SG will post a notice of said amendment at <https://ofy-sg.org/notices/rfp/>.

RFP No. 212 was amended on May 29, 2020 to add additional items to the scope of work.

The items in this Amended Scope of Work are additions to the original scope of work in the RFP.